



**NOTES:**

V.S. SHALL TAP THE WATER MAIN, LAY TUBING AND INSTALL FITTINGS. EXCAVATION AND BACKFILL SHALL BE BY OTHERS  
 SERVICE SHALL BE LAID PERPENDICULAR FROM THE WATER MAIN TO THE PROPERTY LINE  
 THERE SHALL BE A HORIZONTAL SEPARATION OF 10' FROM ANY SEWER LINE AND 5' FROM ANY OTHER UTILITY LINE  
 THE SERVICE SHALL BE FLUSHED BEFORE ACTIVATING TO AVOID METER CLOGGING.  
 TRENCH SHALL NOT BE BACKFILLED UNTIL SERVICE HAS BEEN INSPECTED AND APPROVED BY VWS. WATER SHALL BE TURNED ON BY VWS ONLY AFTER APPROVAL AND IN ACCORDANCE WITH SERVICE APPLICATION.  
 ALL COMPACTION SHALL BE BY MECHANICAL MEANS

NEW AND RENEWED SERVICES SHALL HAVE REMOTE READERS  
 METER SHALL BE SIZED AND INSTALLED BY VWS AS CLOSE TO THE SERVICE ENTRY AND INLET VALVES AS POSSIBLE  
 FLANGES WILL BE PROVIDED BY VWS FOR METERS 1 1/2" AND GREATER. TAIL PIECE PROVIDED BY VWS FOR METERS 1" AND SMALLER.

VALLEY WATER SYSTEMS, INC.	
SCALE: NTS	DRAWN BY: MJB
DATE: 3-21-05	APPROVED BY:
DOMESTIC SERVICE DETAIL	
DRAWING No.:	VWS-2